This article was downloaded by: *[Harvard College]*
On: *6 May 2009*
Access details: *Access Details: [subscription number 908310102]*
Publisher *Psychology Press*
Informa Ltd Registered in England and Wales Registered Number: 1072954 Registered office: Mortimer House, 37-41 Mortimer Street, London W1T 3JH, UK

The Quarterly Journal of Experimental Psychology
Publication details, including instructions for authors and subscription information:
http://www.informaworld.com/smpp/title~content=t716100704

Primitive computations in speech processing

Ansgar D. Endress [a]; Jacques Mehler [b]
[a] Harvard University, Cambridge, MA, USA [b] International School for Advanced Studies, Trieste, Italy

First Published on: 02 May 2009

To cite this Article Endress, Ansgar D. and Mehler, Jacques(2009)'Primitive computations in speech processing',The Quarterly Journal of Experimental Psychology,

To link to this Article: DOI: 10.1080/17470210902783646

URL: http://dx.doi.org/10.1080/17470210902783646

PLEASE SCROLL DOWN FOR ARTICLE

Full terms and conditions of use: http://www.informaworld.com/terms-and-conditions-of-access.pdf

This article may be used for research, teaching and private study purposes. Any substantial or systematic reproduction, re-distribution, re-selling, loan or sub-licensing, systematic supply or distribution in any form to anyone is expressly forbidden.

The publisher does not give any warranty express or implied or make any representation that the contents will be complete or accurate or up to date. The accuracy of any instructions, formulae and drug doses should be independently verified with primary sources. The publisher shall not be liable for any loss, actions, claims, proceedings, demand or costs or damages whatsoever or howsoever caused arising directly or indirectly in connection with or arising out of the use of this material.

THE QUARTERLY JOURNAL OF EXPERIMENTAL PSYCHOLOGY
i*First*, 1–23

Psychology Press
Taylor & Francis Group

Primitive computations in speech processing

Ansgar D. Endress
Harvard University, Cambridge, MA, USA

Jacques Mehler
International School for Advanced Studies, Trieste, Italy

Previous research suggests that artificial-language learners exposed to quasi-continuous speech can learn that the first and the last syllables of words have to belong to distinct classes (e.g., Endress & Bonatti, 2007; Peña, Bonatti, Nespor, & Mehler, 2002). The mechanisms of these generalizations, however, are debated. Here we show that participants learn such generalizations only when the crucial syllables are in edge positions (i.e., the first and the last), but not when they are in medial positions (i.e., the second and the fourth in pentasyllabic items). In contrast to the generalizations, participants readily perform statistical analyses also in word middles. In analogy to sequential memory, we suggest that participants extract the generalizations using a simple but specific mechanism that encodes the positions of syllables that occur in edges. Simultaneously, they use another mechanism to track the syllable distribution in the speech streams. In contrast to previous accounts, this model explains why the generalizations are faster than the statistical computations, require additional cues, and break down under different conditions, and why they can be performed at all. We also show that that similar edge-based mechanisms may explain many results in artificial-grammar learning and also various linguistic observations.

Keywords: Artificial-grammar learning; Serial memory; Language acquisition.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Traditionally, the mind has been seen as capable of formal symbolic operations (e.g., Fodor, 1975, 1983; Fodor & Pylyshyn, 1988; Lehman, Laird, & Rosenbloom, 1998; Newell, 1980, 1990), which has led many researchers to liken it to a computer. On the other hand, there is overwhelming evidence, in part from the artificial-language-learning literature, that humans and other animals have sophisticated statistical abilities (e.g., Aslin, Saffran, & Newport, 1998; Hauser, Newport, & Aslin, 2001; Saffran, Aslin, & Newport, 1996). However, it is still unclear under which conditions symbolic and statistical processes operate and if (and how) they interact. A situation where both statistical and nonstatistical operations can be observed simultaneously would thus help to clarify these questions.

Such an experimental paradigm has been devised by Peña, Bonatti, Nespor, and Mehler (2002). Theirs and subsequent studies suggest that

Correspondence should be addressed to Ansgar D. Endress, Harvard University, William James Hall 984, 33 Kirkland St, Cambridge MA 02138, USA. E-mail: ansgar.endress@m4x.org

This research was supported by Grant L.R. 3/98 from the Regione Friuli Venezia Giulia, by the McDonnell Foundation Grant 21002089, and by the European Commission Special Targeted Project CALACEI (Contract No. 12778 NEST). We are grateful to Á. Kovács for helpful discussions and suggestions.

© 2009 The Experimental Psychology Society

http://www.psypress.com/qjep
DOI:10.1080/17470210902783646

Downloaded By: [Harvard College] At: 19:16 6 May 2009

participants may learn a regularity defined over syllable classes, while simultaneously performing complex statistical operations (Endress & Bonatti, 2007). However, the mechanisms of the generalizations remained elusive despite substantial research (e.g., Balaguer, Toro, Rodriguez-Fornells, & Bachoud-Lévi, 2007; Mueller, Bahlmann, & Friederici, 2008; Pacton & Perruchet, 2008; Perruchet, Tyler, Galland, & Peereman, 2004; Seidenberg, MacDonald, & Saffran, 2002). A particularly important issue concerns the question of whether these results can be explained by a single, associationist mechanism, or whether one needs to posit different kinds of mechanisms for the generalizations and the statistical computations, respectively. Here, we ask what participants learned in these experiments, hoping that answers to this question will also provide clues to the underlying learning mechanisms.

In the aforementioned experiments, participants may have extracted generally applicable classes (like nouns and verbs in language) and may have learned where in words these have to occur. Alternatively, they may have learned the *positions* of certain syllables without extracting any classes at all; participants may have learned that one syllable set had to occur in word-onsets, while another syllable set had to occur in word-offsets, without these sets being classes in any meaningful sense.

These possibilities can be tested by noting that the crucial syllables in the aforementioned experiments always occurred in the word-edges. Research on sequential memory suggests, however, that edges are particularly well suited to learn the positions of items because all positions are encoded relative to the sequence-edges (see, e.g., Henson, 1998, for a review). If participants simply encoded the sequential positions of the syllables, we would thus expect the generalizations to exhibit the hallmarks of positional memory mechanisms. Participants thus should learn similar regularities well when the crucial syllables are in edges, but much less so when they are in other positions. If participants had extracted generally applicable classes such as nouns and verbs, in contrast, they should also learn similar regularities in the other positions. After all, linguistic classes are not limited to edge positions either. We thus ask whether similar regularities can be learned only when the crucial syllables are in the word-edges, or also when they are located in other positions.

These predictions can also be derived by considering the kinds of grammatical processes that may be mirrored by Endress and Bonatti's (2007) results. On the one hand, participants may have learned grammatical classes, such as nouns and verbs, and a rule-like dependency between these classes, such as the fact that the object of a transitive word is a noun. If so, generalizations should be observed both when the crucial syllables are in word-edges and when they are in word-middles. In contrast, if participants just learned that certain syllables had to occur word-initially and others word-finally, such regularities are more likely to reflect affixation rules, such as the English past tense, where the [ed] suffix has to occur word-finally. If so, the generalizations should be much easier to extract in edge positions than in middle positions, since, as we show below, virtually all linguistic regularities that appeal to the positions of items (including affixation) are defined relative to the edges of some linguistic constituents. It is thus possible that, to encode the sequential positions of items, language may use edge-based mechanisms similar to those uncovered in memory research. Here, we start addressing this possibility by asking whether such edge-based mechanisms may be the psychological basis of artificial-grammar-learning results such as those by Peña et al. (2002).

A test case for statistical and nonstatistical operations

Statistical and nonstatistical computations are usually investigated separately (e.g., Marcus, Vijayan, Rao, & Vishton, 1999; Saffran et al., 1996), which may make them seem contradictory rather than complementary. In some cases, however, both statistical and more abstract information could be observed in the same experiment. For example, Gómez and Gerken (1999) familiarized 12-month-old infants

Downloaded By: [Harvard College] At: 19:16 6 May 2009

with strings of non-sense syllables (such as PEL–TAM–PEL–JIC). These strings were generated by a finite-state grammar similar to those in artificial-grammar-learning studies with adults (e.g., Miller, 1958; Reber, 1967, 1969). After this familiarization, Gómez and Gerken (1999) showed that infants detected both item-specific information from the strings and more abstract information. When tested on new strings, they discriminated "legal" strings conforming to the grammar from those with illegal final syllables or illegal syllable bigrams. Infants had also acquired more abstract knowledge from the strings. They could discriminate legal strings from illegal ones even when the strings were implemented using new syllables that the infants had not heard during familiarization.

Another paradigm where statistical and nonstatistical computations could be observed was devised by Peña et al. (2002). They familiarized participants with continuous speech streams composed of a sequence of non-sense words, and asked under which conditions statistical and nonstatistical computations could be observed. In short, while they observed statistical computations under all familiarization conditions, nonstatistical generalizations were observed only when the words in the stream were separated by short silences. Peña et al. (2002) initially suggested that participants had learned a rule-like dependency between the first and the last syllables of each word; Endress and Bonatti (2007) subsequently showed that participants had rather learned which syllables could occur word-initially, and which could occur word-finally, again only when words were separated by small silences. As the experiments presented here are modelled after those by Peña et al. (2002) and Endress and Bonatti (2007), we now describe their crucial experiments in more detail; these experiments as well as the test items used are summarized in Tables 1 and 2, respectively.

Peña et al. (2002) familiarized participants with a monotonous stream of trisyllabic non-sense words. In each non-sense word (henceforth just "word"), the first syllable predicted the last syllable with certainty; the middle syllables, in contrast, varied, yielding words of the form A_iXC_i. (We use the term "word" just to designate statistically coherent syllable sequences, but do not imply any prosodic or syntactic properties that real words may have.) In line with much research showing that learners can use co-occurrence statistics among syllables such as transitional probabilities (TPs)[1] to extract words from fluent speech (e.g., Aslin et al., 1998; Saffran, 2001; Saffran et al., 1996), also participants in Peña et al.'s (2002) experiments could use the statistical dependency between the first and the last syllables of words to segment the stream. However, they could not generalize this dependency to new items. Generalization was tested by having participants choose between *rule-words* and *part-words* (see Table 2). Rule-words had the structure $A_iX'C_i$; they conformed to the dependency between the first and the last syllables but had a middle syllable that had never occurred in this position during the stream. Part-words did occur in the stream but straddled a word boundary (e.g., by taking the last syllable from one word and the first two syllables from a following word) and thus did not conform to the regularity between the first and the last syllables. As rule-words did not occur in the stream while part-words did, participants can prefer rule-words to part-words only if they generalize the dependency between the first and the last syllables.

When familiarized with a continuous speech stream, participants could not use the statistical regularities in the stream for generalizing the dependency between the first and the last syllables of words, even when exposed to a stream as long as 30 min. When words in the stream were separated by short, probably subliminal, silent pauses of 25 ms, in contrast, participants generalized the dependency after a familiarization of only 2 min. Apparently, these subliminal segmentation cues

[1] TPs are conditional probabilities on syllable sequences. For two syllables σ_1 and σ_2, for example, $TP(\sigma_1 \rightarrow \sigma_2) = P(\sigma_1\sigma_2)/P(\sigma_1)$, where the probabilities are estimated by the corresponding frequencies.

Table 1. *Summary of the main experiments of Peña et al. (2002) and Endress and Bonatti (2007)*

Experiment	*Silence between words in stream*	*Stream duration (in minutes)*	*Test items*	*Preference for*
PBMN,[a] Exp. 1	−	10	Words vs. part-words	Words
PBMN, Exp. 2	−	10	Rule-words vs. part-words	None
PBMN, Exp. 3	+	10	Rule-words vs. part-words	Rule-words
PBMN, Exp. 4	−	30	Rule-words vs. part-words	Part-words
PBMN, Exp. 5	+	2	Rule-words vs. part-words	Rule-words
EB,[b] Exp. 1	+	10	Class-words vs. part-words	Class-words
EB, Exp. 2	−	10	Class-words vs. part-words	No preference
EB, Exp. 3	+	2	Class-words vs. part-words	Class-words
EB, Exp. 4	+	30	Class-words vs. part-words	No preference
EB, Exp. 5	+	60	Class-words vs. part-words	Part-words
EB, Exp. 12	+	2	Rule-words vs. class-words	Rule-words
EB, Exp. 13	−	10	Rule-words vs. class-words	Rule-words

[a]PBMN: Peña et al. (2002). [b]EB: Endress and Bonatti (2007).

Downloaded By: [Harvard College] At: 19:16 6 May 2009

were required for the generalizations to be drawn. According to Peña et al. (2002), these silences provided the stream with some minimal bracketing cues, similar to prosodic cues that mark constituent boundaries in real speech. (We come back to the probable role of the silences later.)

What were the generalizations that participants extracted? On the one hand, they might have generalized the aforementioned dependency between the first and the last syllables of words. On the other hand, they may have learned that certain syllables had to occur word-initially and others

Table 2. *Summary of the main test item types used*

	Words	*Part-words*	*Rule-words*	*Class-words*
	ITEMS USED BY PEÑA ET AL. (2002) AND ENDRESS AND BONATTI (2007)			
	$\mathbf{A_i}X\mathbf{C_i}$	$\mathbf{C_i}\|\mathbf{A_j}X$ or $X\mathbf{C_i}\|\mathbf{A_j}$	$\mathbf{A_i}X'\mathbf{C_i}$	$\mathbf{A_i}X'\mathbf{C_j}$
	ITEMS USED IN THE CURRENT EXPERIMENTS			
Edge condition	$\mathbf{A_i}XYZ\mathbf{C_i}$	$YZ\mathbf{C_i}\|\mathbf{A_j}X$ or $Z\mathbf{C_i}\|\mathbf{A_j}XY$	$\mathbf{A_i}X'Y'Z'\mathbf{C_i}$	$\mathbf{A_i}X'Y'Z'\mathbf{C_j}$
Middle condition	$X\mathbf{A_i}Y\mathbf{C_i}Z$	$\mathbf{C_i}Z\|X\mathbf{A_j}Y$ or $Y\mathbf{C_i}Z\|X\mathbf{A_j}$	$X'\mathbf{A_i}Y'\mathbf{C_i}Z'$	$X'\mathbf{A_i}Y'\mathbf{C_j}Z'$
	EXPLANATION			
	Appear in the stream $TP(A_i \rightarrow C_i) = 1$	Appear in the stream but straddle a word boundary	As words, but with new X, Y, and Z syllables	As rule-words, but with first and last syllables from different families
		Violate dep. between 1st and last syllables	Respect dep. between 1st and last syll	Violate dep. between 1st and last syllables
		Violate class-based regularity	Respect class-based regularity	Respect class-based regularity

Notes: TP = transitional probability. Bold characters indicate the syllables critical for the generalizations. The location where the word boundaries fell during familiarization is shown by | ; no boundaries were present in the test items.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

word-finally—irrespective of any dependency between particular first and last syllables. If so, they may have learned that the first and the last syllables of words had to belong to distinct syllable classes, the classes being the sets of syllables that could occur in these respective positions. We call this regularity a *class-rule*. (In the following, we argue that these classes are merely the lists of items that can occur word-initially and word-finally and not classes such as nouns and verbs; for consistency with Endress and Bonatti's, 2007, wording, however, we keep the class-terminology.)

To evaluate this possibility, Endress and Bonatti (2007) familiarized participants with syllable streams as in Peña et al.'s (2002) experiments. Recall that words had the structure A_iXC_i, where the "A" and "C" syllables came from different families. After familiarization, participants had to choose between *class-words* and part-words. Class-words had the structure $A_iX'C_j$, where A_i and C_j belonged to different families, and X' had occurred in the familiarization stream but never in word-medial positions (that is, it was either an "A" or a "C" syllable); class-words thus conformed to the class rule (as the initial and the final syllables belonged to the appropriate syllable sets) but never occurred during the familiarization streams (in fact, their constituent syllables came from three different words). As mentioned above, part-words occurred in the stream but straddled a word boundary and thus did not conform to the class-rule. Only if participants generalized the class-rule should they prefer class-words to part-words.

Participants preferred class-words to part-words when familiarized with segmented streams with 25-ms silences between words, but not after familiarizations with continuous streams, suggesting that the subliminal segmentation cues induced participants to extract the class-rule. Endress and Bonatti (2007) then familiarized participants with segmented streams of various durations. When familiarized with a 2-min stream, participants preferred class-words to part-words; in contrast, when familiarized with a 60-min stream, they preferred part-words to class-words. In between, the preference for class-words was negatively correlated with the familiarization duration.

Endress and Bonatti (2007) investigated also whether participants could track statistical information in the speech streams. They familiarized participants with the same streams as before, but then asked them to choose between rule-words and class-words. (As mentioned above, rule-words are similar to words from the speech stream but have a new middle syllable; class-words differ from rule-words in that their first and last syllables come from different families. The crucial difference between these test items is thus that the first syllable predicts the last one with probability 1.0 in rule-words, while this probability is 0 in class-words.) Rule-words were preferred to class-words after both segmented and continuous familiarizations, suggesting that participants could track statistical information in either familiarization condition.

Endress and Bonatti (2007) interpreted these results as evidence for an interaction between two mechanisms: A rapid, nonstatistical, mechanism may extract the class-rule; this mechanism may explain why participants prefer class-words initially. A second, statistical, mechanism may track the syllable distribution; this mechanism should also mediate the familiarity with part-words, which should be strengthened over time. In contrast, no such strengthening should occur for the familiarity with the class-rule, since it may be at ceiling early on. Hence, only the familiarity with part-words but not that with class-words should be strengthened over time; the preference for class-words compared to part-words should thus disappear for long familiarizations.

It has remained an open question, however, why the generalizations were faster than the statistical computations, why they required additional segmentation cues, and why they could be learned in the first place. Accordingly, the conclusion that participants analyse the speech streams with qualitatively different mechanisms has met with considerable resistance. For example, it has been suggested that general statistical mechanisms can account for these results without the need to postulate multiple mechanisms (e.g., Perruchet et al.,

2004; Seidenberg et al., 2002). By clarifying the mechanisms of the generalizations, we hope to provide answers also to these questions.

What kinds of classes did participants learn?

While Endress and Bonatti (2007) suggested that participants had learned a regularity entailing syllable classes, a vast literature suggests that it is extremely difficult to demonstrate class-learning in artificial-grammar-learning experiments. Where class-learning has been observed, the effects were typically weak and relied on the availability of multiple convergent cues (e.g., Braine, 1987; Gerken, Wilson, & Lewis, 2005; Gómez & Lakusta, 2004; Mintz, 2002; Monaghan, Chater, & Christiansen, 2005; Redington, Chater, & Finch, 1998). One may thus be suspicious whether Endress and Bonatti's (2007) classes were classes in the sense of nouns and verbs, or whether there may be a simpler interpretation.

One possible interpretation is that participants have learned the positions of the crucial syllables; they may just have learned which syllable sets occurred in the first and the last positions. This interpretation is made plausible by the observation that the crucial syllables were always located in the word-edges, as it has been shown that edges are particularly conducive to learning regularities involving the positions of items.

To see why edges are well suited for learning positional regularities, it is necessary to consider the kinds of memory that can be used to encode sequences (see Henson, 1998, 1999, for reviews). On the one hand, sequences such as ABCD can be encoded by remembering the transitions $A \rightarrow B$, $B \rightarrow C$ and $C \rightarrow D$; this form of memory is strongly related to the transitional probabilities investigated in the literature following Saffran et al. (1996). On the other hand, one can remember that A came first, D last, and B in the second position. Among many other observations suggesting that these two modes of sequential memory are distinct and independent, the most striking one are maybe intrusion errors, a frequent mistake in memory experiments. Participants can make such errors when recalling multiple sequences such as ABCD and EFGH. Under these circumstances, they sometimes recall an element in an incorrect sequence—but in its correct position. For example, they may erroneously recall the sequences E*B*GH instead of E*F*GH. Although the item B never occurred with any of the items of the sequence it was recalled in, it kept its correct position from its original sequence. These and many other observations suggest that memory for positions is distinct and at least partially independent from other forms of sequential memory, and that positions must be encoded in a sufficiently abstract way so that they can be generalized from one sequence to another (e.g., Hicks, Hakes, & Young, 1966; Schulz, 1955).

Further research suggests that positions are encoded relative to sequence-edges as anchor points. In fact, according to most recent models of memory for sequential positions, items in a sequence become linked to edge-based, positional codes (whose implementation vary widely among models), and their position is encoded relative to these edge-based codes (e.g., Henson, 1998; Hitch, Burgess, Towse, & Culpin, 1996; Ng & Maybery, 2002). Moreover, it has previously been shown in other artificial-grammar-learning experiments that regularities appealing to the positions of items are learned much more easily when the crucial items occur in the sequence-edges than when they occur in other positions (e.g., Endress & Mehler, in press; Endress, Scholl, & Mehler, 2005); it is thus plausible that this may be the case also for Peña et al.'s (2002) and Endress and Bonatti's (2007) experiments.

If participants in these experiments tracked the positions of items, their generalizations would amount to having learned which syllables had to occur in the word-edges. If so, we would expect similar generalizations as long as the crucial syllables (whose positions are to be memorized) are in the edges, but not if they are located in other positions. In contrast, if participants had learned classes such nouns and verbs, one would also expect them to generalize if the crucial syllables are located in other positions; after all, linguistic classes such as nouns and verbs are not restricted to edge positions either.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Note that, even if the aforementioned generalizations reflect that participants have encoded (and generalized) the positions of certain syllables, they may still reflect language-related processes. Indeed, as we show in more detail in the General Discussion, almost all linguistic regularities appealing to the positions of items are defined relative to the edges of some constituents. Hence, it is possible that a simple memory process such as the one encoding the positions of items in a sequence may be used for a wide variety of linguistic computations.

The current experiments

In the experiments presented below, we ask whether the generalizations observed by Peña et al. (2002) can be explained by an edge-based mechanism, or whether they may also be available in other positions. The test items and experiments are summarized in Tables 2 and 3, respectively. We asked whether participants can extract a class-based rule in longer words when the crucial syllables are located either in edge positions or in nonedge positions. Participants were familiarized with a segmented stream of pentasyllabic items. In Experiment 1a, we asked whether they could learn that the first and the last syllables of words had to belong to distinct syllable classes. Experiment 1b asked the same question for the second and the fourth positions (such that the crucial syllables were no longer in edge positions). Experiment 2 asked whether such generalizations would also be possible when participants were familiarized with continuous streams. If participants had learned classes such as nouns and verbs, they should generalize fairly well also when the crucial syllables were located in word-middles. In contrast, if they had simply encoded the positions of the crucial syllables, the generalizations should be much stronger when the crucial syllables are in the word-edges. Finally, Experiment 3 tested whether participants could perform statistical computations in word-middles.

EXPERIMENT 1A: GENERALIZATIONS IN WORD-EDGES

This experiment asked whether participants can learn a class-based regularity in pentasyllabic words when the critical syllables are located in the word-edges. Participants were familiarized with a concatenation of words with the structure $\mathbf{A_i}XYZ\mathbf{C_i}$; words in this stream were separated by silences. In each word, the first syllable predicted the last syllable with certainty, while the middle syllables were variable. The structure of the words was thus analogous to those used by Peña et al. (2002), except that they had three (instead of one) middle syllables (see Table 2). As in Peña et al.'s (2002) experiments, the crucial "A" and "C" syllables were located in word-edges.

Participants were told that they would listen to a monologue in Martian (a made-up language). After this familiarization, they were presented with pairs of items. As the purpose of the present experiment was to investigate the psychological mechanisms of the fast, class-based generalizations observed by Endress and Bonatti (2007), we chose similar test items as in their experiments; participants thus had to choose class-words and part-words. In each trial, they

Table 3. *Summary of the experiments*

Exp.	*Silence between words in stream*	*Position of crucial syll.*	*Word*	*Test items*	*Preference for*
1a	+	First, last	$\mathbf{A_i}XYZ\ \mathbf{C_i}$	Class-words vs. part-words	Class-words
1b	+	2nd, 4th	$X\mathbf{A_i}Y\mathbf{C_i}Z$	Class-words vs. part-words	None
2[a]	−	First, last	$\mathbf{A_i}XYZ\mathbf{C_i}$	Class-words vs. part-words	Part-words
	−	2nd, 4th	$X\mathbf{A_i}Y\mathbf{C_i}Z$	Class-words vs. part-words	Part-words
3	+	2nd, 4th	$X\mathbf{A_i}Y\mathbf{C_i}Z$	Rule-words vs. class-words	Rule-words

[a]The conditions with the first and the last syllables as crucial syllables and with the second and fourth syllables as crucial syllables were run as within-subject conditions in Experiment 2. Bold characters indicate the syllables critical for the generalizations.

had to decide which of these items sounded more Martian-like. As mentioned above, class-words conformed to the class-based regularity, but they did not appear in the speech stream. Their first and last syllables had occurred in these respective positions but never in the same word; their middle syllable had never occurred in middle positions during familiarization. Part-words, in contrast, did occur during the stream but straddled a word boundary and thus did not conform to the class-rule. If participants had learned that the first and the last syllables had to be members of distinct classes (where the "classes" may be merely the lists of syllables that can occur in these positions), they should prefer class-words to part-words, but not otherwise.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Method

Participants

A total of 14 French participants (7 females, 7 males, mean age 24.2 years, range 19–34 years) took part in this experiment for monetary reward.

Apparatus

All experiments were run on a PC using Presentation® software. Participants were tested individually in a quiet room. Stimuli were presented over headphones. Responses were collected on premarked keys on a keyboard.

Familiarization

Participants were familiarized with a syllable stream of 3.45 min constructed from a concatenation of non-sense words (henceforth just "words"). Participants were informed that they would hear a monologue in Martian and that they would have to discover the words it contained.

Words had the structure A_iXYZC_i, where the "A" and "C" syllables belonged to four different $A_i \ldots C_i$ combinations (called "families": ba. . .de, fu. . .gi, mʏ. . .lo, Ri. . .na). The "X", "Y", and "Z" syllables were filler syllables (as the "X" syllables in Peña et al.'s, 2002, words). Three syllables could appear in each of the "X", "Y", and "Z" positions (X: /fa/, /Re/, /zu/; Y: /do/, /lʏ/, /ne/; Z: /bo/, /gu/, /zi/). The transition probabilities (TPs) between "X" and "Y" syllables and between "Y" and "Z" syllables were .5, those between "A" and "X" syllables .33, and those between "Z" and "C" syllables .25; TPs across word boundaries were .33. Concerning the higher order TPs, the first syllable predicted the last syllable with certainty (i.e., the corresponding TP was 1.0) while the other TPs were much smaller. The stream contained two repetitions of each of the 48 words; no syllable could appear in two consecutive words.

In contrast to Peña et al. (2002) and Endress and Bonatti (2007), where words in the segmented streams were separated by 25-ms silences, pilot studies revealed that such silences would not be sufficient for inducing generalizations in pentasyllabic words, maybe due in part to their more complex statistical structure, or to the prosodic implausibility of flat five-syllable items. We thus used clearly perceptible silences of 1 s.

The stream was synthesized using the fr2 (French female) diphone base of MBROLA (Dutoit, Pagel, Pierret, Bataille, & van der Vreken, 1996). It was synthesized with an increasing amplitude ramp in the first 5 s and a decreasing amplitude ramp in the last 5 s. This ensures that the stream fades in and out at no point corresponding to either words or part-words. (In this experiment, the silences gave clearly perceptible cues to word onsets, but we used the ramping manipulation nevertheless to keep the material as close as possible to that of Experiment 2, where the speech stream was continuous.) Syllables had a duration of 232 ms and a fundamental frequency of 200 Hz.

Test

Participants had to choose between class-words and part-words (see below and Table 2); they had to decide which of these alternatives was more likely to be a Martian word. Test items were synthesized using the fr2 diphone base of MBROLA (Dutoit et al., 1996) with the same parameters as those for the familiarization stream.

Class-words had the form $A_iX'YZ'C_j$. As A_i and C_j belonged to different families, the TPs between the first and the last syllables were 0 (instead of 1 as during the familiarization); still,

these syllables appeared in the positions in which they had been encountered during familiarization (that is, in the first and the last positions in words, respectively) and thus conformed to the class-rule. Y syllables were the same as those in the familiarization stream. Finally, the X′ and Z′ syllables have never appeared in their respective positions during familiarization but were "A" or "C" syllables from the stream; hence, class-words could have one of the following structures: $A_iA_kYA_lC_j$, $A_iA_kYC_lC_j$ and $A_iC_kYA_lC_j$, $A_iC_kYC_lC_j$, which were equally represented in the test pairs. All "A" and "C" syllables in a class-word came from different families.

Part-words could have one of the following structures: $XYZC_i|A_j$, $YZC_i|A_jX$, $ZC_i|A_jXY$ and $C_i|A_jXYZ$, where the vertical bars indicate the positions of word boundaries during the familiarization (although no boundaries were present in part-words during test). We used only two types of part-words, namely $YZC_i|A_jX$ and $ZC_i|A_jXY$, because "A" and "C" syllables would appear in the edges of the other part-word types. We used 24 test pairs presented once in random order. In each pair, the class-words shared the "A", "C", and "Y" syllables with the part-word. Half of the trials started with a class-word and the other half with a part-word. Appendix A lists all test pairs.

Results

As shown in Figure 1, participants preferred class-words to part-words (percentage of preference for class-words: $M = 63.7\%$, $SD = 9.9\%$), $t(13) = 5.2$, $p < .0002$, Cohen's $d = 1.4$, confidence interval, $CI_{.95} = 58.0\%, 69.39\%$; the preference for class-words did not differ depending on the part-word type in a test pair, $t(13) = 0.2$, $p = .813$, Cohen's $d = 0.07$, *ns* (paired *t* test). (Statistical tests are two-tailed throughout this article; *t* tests are reported with respect to a chance level of 50%.)

EXPERIMENT 1B: GENERALIZATIONS IN WORD-MIDDLES

Experiment 1b was almost identical to Experiment 1a except that participants had to learn that "A" and "C" syllables had to belong to distinct classes in words with the form XA_iYC_iZ (rather than A_iXYZC_i as in Experiment 1a); in other words, the critical syllables were now word-medial rather than in word-edges. Again, the particularity of the relation between each A_i and its C_i was that the TP between these syllables was 1.0. We thus asked whether participants could learn that the second and the fourth positions in words had to belong to distinct classes (noting again that these classes may be merely the lists of syllables that can occur in these positions). In contrast to Experiment 1a, where the crucial syllables were in edges, the crucial syllables were now in middles. After familiarization with a speech stream, participants had again to choose between class-words and part-words.

Method

Participants

A total of 14 French participants (8 females, 6 males, mean age 25.9 years, range 18–58 years) took part in this experiment for monetary reward.

Familiarization

The familiarization stream was constructed as in Experiment 1a, except that words had the structure XA_iYC_iZ such that the critical syllables were no longer in the edges. The assignment of the syllables to the different positions (X, A, Y, C, and Z) was mostly the same as that in Experiment 1a. In order to avoid French words in the stimuli, /na/ has been used as a "Z" syllable rather than "C" syllable, /zi/ as a "C" syllable rather than a "Z" syllable, /fa/ as a "Z" syllable rather than an "X" syllable, and /gu/ as an "X" syllable rather than a "Z" syllable.

The TPs between adjacent syllables were .25 or .33 within words, and .33 between words; also the higher order TPs were much lower than 1.0 (that is, the TP between "A" and "C" syllables). As it turned out to be impossible to generate a stream that controlled all TPs exactly, in particular between "Z" and "X" syllables, we included the frequency of these transitions in the data analysis to assess their influence.

Downloaded By: [Harvard College] At: 19:16 6 May 2009



Figure 1. *Results of Experiments 1 and 2. Bars represent sample averages, error bars standard errors from the mean, and the dotted line the chance level of 50%. After familiarization with a segmented speech stream, participants learn the class-rule only when the critical syllables are located in the word-edges (Experiment 1a) but not when they are located in word-middles (Experiment 1b). When familiarized with continuous streams, in contrast, participants preferred part-words both in edges and in middles (Experiment 2).*

Test

Also in this test phase, participants had to choose between class-words and part-words; again, they should prefer class-words only if they extracted the class-rule.

Class-words had the form $X'A_iYC_jZ'$, where X' and Z' were in reality "A" and "C" syllables and had never appeared in initial or final positions during familiarization. As in Experiment 1a, A_i and C_j belonged to distinct families; the TPs between the "A" and "C" syllables were thus broken. Still, since these syllables appeared in the positions in which they were encountered during familiarization, class-words respected the class-rule. Importantly, in contrast to Endress and Bonatti's (2007) experiments and Experiment 1a, the crucial syllables occurred in middles rather than in edges.

Class-words could have one of the following structures: $A_kA_iYC_jA_l$, $A_kA_iYC_jC_l$, $C_kA_iYC_jA_l$, or $C_kA_iYC_jC_l$; each of these structures appeared equally often in the test pairs. Part-words could have the structures $A_iYC_iZ|X$, $YC_iZ|XA_j$, $C_iZ|XA_jY$, and $Z|XA_jYC_j$, but we used only the structures $C_iZ|XA_jY$ and $YC_iZ|XA_j$, because these are the only structures where the "A" and "C" syllables come from different families, and where the "X" and "Z" syllables do not occur in edges, and because the word boundaries in these part-words were at the same positions as in Experiment 1a (that is, between the second and the third syllables, or between the third and the fourth syllables). Each part-word type was represented equally in the test pairs. In each test pair, both test items shared the "A", "C", and "Y" syllables.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Downloaded By: [Harvard College] At: 19:16 6 May 2009

We assessed the influence of the frequency of the transitions between "Z" and "X" syllables in part-words by forming a "frequent" group of part-words with an average TP of .416 between "Z" and "X" and a "rare" group with an average TP of .168 between "Z" and "X", and we included this factor in the data analysis. Appendix B shows the test pairs used in Experiment 1b. Test pairs were presented in random order.

Results

As shown in Figure 1, participants had no preference for class-words ($M = 48.2\%$, $SD = 12.1\%$), $t(13) = 0.6$, $p = .59$, Cohen's $d = 0.15$, $CI_{.95} = 41.2\%, 55.2\%$, *ns*. A repeated measure analysis of variance (ANOVA) with the intrasubject factors part-word type and frequency of the transitions in part-words revealed no main effect of the part-word type, $F(1, 13) = 1.3$, $p = .269$, $\eta_p^2 = .09$, *ns*, nor of the frequency of the transitions, $F(1, 13) = 1.4$, $p = .264$, $\eta_p^2 = .09$, *ns*; neither did the interaction between these factors reach significance, $F(1, 13) < .01$, $p = .928$, $\eta_p^2 < .01$, *ns*.

The preference for class-words was higher in Experiment 1a than in Experiment 1b, $F(1, 26) = 13.8$, $p < .001$, $\eta^2 = .35$.

Discussion

Experiments 1a and 1b investigated whether the extraction of a class-based regularity from a speech stream such as the one observed by Endress and Bonatti (2007) is limited to word-edges, or whether it can be observed also in word-medial positions. This would allow us to determine whether participants had learned classes such as nouns and verbs (that should not be limited to edge-positions), or whether they had generalized the positions of the crucial syllables by mechanisms of positional memory (in which case the generalizations should be observed primarily in edges).

In Experiments 1a and 1b, participants had to learn that the "A" and "C" syllables had to belong to different classes in words with the structure $\mathbf{A_iXYZC_i}$ (where the critical syllables were in the edges; Experiment 1a) or in words with the structure $\mathbf{XA_iYC_iZ}$ (where the critical syllables were in word-medial positions; Experiment 1b). Participants preferred class-words to part-words in Experiment 1a (where the critical syllables were in the edges), but not in Experiment 1b (where the critical syllables were in word-middles). These results suggest that participants learned the positions of the crucial syllables by the edge-based mechanisms of positional memory, rather than extracting general classes such as nouns and verbs.

Of course, given the small effect size in Experiment 1b, the statistical power is low with only 14 participants; in fact, the power is only 8%. However, given this effect size, one would need at least 362 participants to achieve a power of at least 80%. It thus seems that, even if we did not detect a significant effect in Experiment 1b due to our small sample size, this effect, if it exists, was much smaller in Experiment 1b than in Experiment 1a. As discussed below in more detail, this is in fact the prediction of our central conclusion: It is much easier to generalize the positions of syllables when the critical syllables are in the word-edges than when they are in word-middles.

Still, participants may not generalize in middles for another reason. In class-words in the middle condition, the edge syllables have not occurred in these positions during familiarization—because they were taken from syllables that occurred only in middles during familiarization. Hence, the edge syllables in class-words may be perceived as "illegal", which may lead participants to reject these items in the middle condition. This may be so, but it highlights again the importance of edges for the participants' choices. If the syllables that occurred in edges during familiarization are not in the appropriate positions during test, participants may well simply reject these items. Violations in other positions, however, seem to be much less important; after all, in class-words in the edge condition, the middle syllables were illegal in just the same way.

In other words, the point of our experiments is not to disprove that positional information can be

tracked in word-middles (which many memory experiments have shown to be possible, at least to some extent). Rather, the generalization items in Endress and Bonatti's (2007) experiments were implemented by having "legal" syllables in some positions, but "illegal" ones in others. Our experiments show that similar generalizations are computed when—as in Endress and Bonatti's (2007) experiments—the legal syllables are in the edges and the illegal ones in middles; in contrast, no such generalizations are observed when the illegal syllables are in edges and the legal ones in middles. Hence, even though participants can also probably track positional information to some extent in word-middles, edges seem to be the predominant positions over which such generalizations are computed.

Finally, one may ask whether participants would generalize in middles with more exposure. This possibility, however, is unlikely. Indeed, Endress and Bonatti (2007) showed that the preference for class-words was negatively correlated with the familiarization duration. More exposure thus hurts the generalization ability, and it is thus unlikely to observe the class-based generalizations in middles after longer familiarizations.

Before concluding that the generalizations that Peña et al. (2002) and Endress and Bonatti (2007) observed were indeed bound to the edge positions, one has to exclude that the participants' preference for class-words differed between Experiments 1a and 1b regardless of the familiarizations. We thus replicated these experiments but by familiarizing participants with continuous speech streams. Since Peña et al. (2002) and Endress and Bonatti (2007) showed that generalizations are observable only after familiarizations with segmented streams, class-words should not be preferred after a familiarization with a continuous stream, neither when the critical syllables are in edges nor when they are in middles. If no generalizations are observed after a familiarization with such a stream, the generalizations in Experiment 1a would seem truly comparable to those observed by Peña et al. (2002) and Endress and Bonatti (2007).

EXPERIMENT 2: GENERALIZATIONS AFTER FAMILIARIZATION WITH CONTINUOUS STREAMS

Experiments 1a and 1b suggest that participants can extract the class-rule much better when the critical syllables are in word-edges than when they are in word middles. Before accepting this conclusion, however, we have to rule out that participants prefer class-words in Experiment 1a (but not in Experiment 1b) independently of the familiarizations. We thus replicated Experiments 1a and 1b but using continuous familiarization streams. Peña et al.'s (2002) and Endress and Bonatti's (2007) results suggest that no generalizations should be observed under these conditions; in their experiments, neither rule-words nor class-words were preferred to part-words unless the familiarization streams were segmented. Hence, unless class-words are intrinsically favoured independently of the familiarization, participants should not prefer class-words when familiarized with a continuous stream.

Method

Participants

A total of 14 French participants (6 females, 8 males, mean age 27.6 years, range 18–44 years) took part in this experiment for monetary reward.

Procedure

The procedure was the same as that in Experiments 1a and 1b with one exception. Each participant took part in two conditions—namely, the replications of Experiments 1a and 1b with continuous familiarizations streams, respectively; the order of these conditions was counterbalanced across participants.

Results

As shown in Figure 1, participants preferred part-words to class-words (preference for class-words: $M = 39.6$ %, $SD = 9.4\%$), $t(13) = 4.2$, $p = .001$, Cohen's $d = 1.1$, $CI_{.95} = 34.1\%, 44.9\%$. A repeated

Downloaded By: [Harvard College] At: 19:16 6 May 2009

measure ANOVA with the condition (critical syllables in edges or middles) as within-subject factor and the order of the conditions (edge condition first or middle condition first) as between-subject factor showed neither a main effect of the condition, $F(1, 12) = 0.328$, $p = .577$, $\eta_p^2 = .03$, *ns*, nor a main effect of the order of the conditions, $F(1, 12) = 0.256$, $p = .622$, $\eta_p^2 = .02$, *ns*, nor an interaction between these factors, $F(1, 12) = 0.15$, $p = .705$, $\eta_p^2 = .01$, *ns*.

In the edge condition, participants tended to prefer part-words (preference for class-words: $M = 41.1\%$, $SD = 16.2\%$), $t(13) = 2.07$, $p = .059$, Cohen's $d = 0.55$, $CI_{.95} = 31.7\%$, 50.4%, with no effect of the part-word type in the test pairs, $t(13) = 0.9$, $p = .39$, Cohen's $d = 0.24$, *ns* (paired *t* test). Also in the middle condition, participants preferred part-words (preference for class-words: $M = 37.9\%$, $SD = 10.8\%$), $t(13) = 4.21$, $p = .001$, Cohen's $d = 1.1$, $CI_{.95} = 31.6\%$, 44.1%. There was no effect of the part-word type in test pairs, $F(1, 13) = 1.19$, $p = .295$, $\eta_p^2 = .08$, *ns*, nor of the frequency of the transitions in the part-words, $F(1, 13) = 0.18$, $p = .682$, $\eta_p^2 = .01$, *ns*, nor an interaction between these factors, $F(1, 13) = 2.6$, $p = .133$, $\eta_p^2 = .165$, *ns*.

Discussion

In Experiment 2, participants preferred part-words to class-words both in the middle and in the edge condition after familiarization with continuous streams. That is, they preferred items that have appeared in the familiarization streams (i.e., the part-words) to those that conformed to the class-rule (i.e., the class-words). These results contrast with Experiments 1a and 1b. In the latter experiments, participants were familiarized with segmented streams; then, during test, they preferred class-words to part-words (and thus generalized the class-based regularities) when the critical syllables were located in edge positions but not when they were located in middle positions. These results are in line with Peña et al.'s (2002) and Endress and Bonatti's (2007) results, who did not observed any generalizations after familiarizations with continuous streams; also here, the silences seem to be required for the generalizations (at least in the edge condition) to be drawn.

While we observed a difference between the edge and the middle conditions when participants were familiarized with a segmented stream (that is, in Experiments 1a and 1b), there was no such effect when participants were familiarized with a continuous stream: After a familiarization with a segmented stream, participants preferred class-words in Experiment 1a but not in Experiment 1b. After a familiarization with a continuous stream, in contrast, there was no difference between the edge condition and the middle condition; participants preferred part-words in both conditions.

Why did participants prefer part-words in Experiment 2 rather than being at chance when familiarized with a continuous stream as in Endress and Bonatti (2007)? The preference for part-words may be due to how the test items have been constructed. Part-words appeared in the familiarization streams while class-words contained syllables from four different words. Participants thus had to choose between very "strange" items and items having appeared in the stream; in the absence of segmentation cues, there are no edges to make the class-words less "strange". Hence, it seems reasonable to expect that participants should prefer part-words, at least after some minimal familiarization.

Still, the silences between words seem to influence the participants' choice also in the middle condition, as they preferred part-words in Experiment 2 but not in Experiment 1b. Does this imply that the silences induce generalizations also in word-middles? This is not necessarily the case. Indeed, it is well known that different cues to word boundaries (such as phonotactics, allophony, or prosody) modulate how speech is segmented (e.g., Jusczyk, Hohne, & Bauman, 1999; Mattys & Jusczyk, 2001; Mattys, Jusczyk, Luce, & Morgan, 1999; Shukla, Nespor, & Mehler, 2007). Shukla et al. (2007) showed, for example, that participants do not prefer words even to "nonwords" when the former straddle prosodic boundaries. As part-words in our experiments straddle word boundaries

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Downloaded By: [Harvard College] At: 19:16 6 May 2009

(and thus the silences) by definition, one would thus expect that they cannot be preferred to class-words after a familiarization with a segmented stream. Importantly, however, this does not explain why class-words are actually preferred in edges but not in middles, suggesting again that some form of generalization must occur under these conditions.

In sum, Experiments 1 and 2 suggest that the segmentation cues in speech streams trigger some generalizations but only in edge positions; also the generalizations observed by Peña et al. (2002) and Endress and Bonatti (2007) may thus be based on such an edge-phenomenon. Below, we interpret these results in terms of specific edge-based positional codes such as those hypothesized in the sequential learning literature (e.g., Henson, 1998). Before, however, we need to rule out another possible confound.

Possibly, participants did not generalize the class-rule when the critical syllables were in word-middles because they simply did not perceive the middle syllables. This interpretation is unlikely for three reasons. First, most sentences are longer than five syllables; if people had problems processing sentence-internal syllables, they would have a hard time understanding any sentence. Second, we showed elsewhere that participants process sequence-internal syllables just as well as syllables in sequences edges even in seven-syllable sequences (Endress et al., 2005); specifically, participants were at ceiling at discriminating seven-syllable sequences irrespective of whether the sequences differed in their edge syllable or in their middle syllables. This suggests that a brute impairment for processing internal syllables cannot be the reason for the failure to observe class-based generalizations in even shorter sequences when the crucial syllables were located in word-middles. Third, to control for the possibility that participants may simply ignore middle syllables when familiarized with segmented streams, Endress and Bonatti (2007) exposed participants again to a segmented stream, but then asked them to choose between words (that occurred in the stream) and rule-words. Rule-words have the structure $A_iX'C_i$; they thus conform to the dependency between the first and the last syllables in words, but they have a middle syllable that has never occurred in this position during the familiarization stream. As the only difference between words and rule-words is the middle syllable, participants should be at chance if they simply ignored the middle syllables. In contrast, participants strongly preferred words to rule-words.

Nevertheless, we perform a control experiment that is interesting for a more theoretical reason. In Peña et al.'s (2002) and Endress and Bonatti's (2007) experiments, participants did not only compute generalizations, but simultaneously analysed the statistical distribution of the syllables in the speech streams. We can thus ask whether similar constraints as for the class-based generalizations apply also to statistical computations: Are such computations possible only in word-edges, or can they be observed also in word-middles? We thus ask whether participants are sensitive to second-order TPs in word-middles; if they are, a brute impairment for processing middle syllables is an unlikely explanation of the failure to find generalizations in word-middles.

EXPERIMENT 3: STATISTICAL COMPUTATIONS IN WORD-MIDDLES

Experiment 3 asked whether statistical computations are constrained in the same way as the class-based generalizations, or whether they can be observed also in word-middles. Participants were familiarized with the stream from Experiment 1b (that is, the segmented stream with the critical syllables in word-middles). During test, they had to choose between rule-words and class-words (see Table 2). Rule-words were identical to class-words except that their "A" and "C" syllables belonged to the same family; they thus had the structure $X'A_iYC_iZ'$ (while class-words had the structure $X'A_iYC_jZ'$). The crucial difference between rule-words and class-words is therefore that the former have a TP of 1 between the second and the fourth syllables, while the latter have a TP of 0 between these syllables.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Using trisyllabic words, Endress and Bonatti (2007) showed that participants prefer rule-words to class-words because of the high TP between the "A" and "C" syllables. If such computations are possible also in word-middles, participants should prefer rule-words to class-words also for pentasyllabic words where the critical syllables are located in word-middles. In contrast, if statistical computations are limited in the same way as the generalizations studied in Experiments 1 and 2, such a preference should not be observable.

Method

Participants

A total of 14 French participants (11 females, 3 males, mean age 23.4 years, range 18–30 years) took part in this experiment for monetary reward.

Familiarization

The familiarization was identical to that of Experiment 1b. That is, the stream was segmented, and the critical syllables appeared in word-middles.

Test

Participants had to choose between rule-words and class-words. Rule-words had the structure $X'A_iYC_iZ'$, where X' and Z' have never occurred in the edge positions during familiarization but were in reality "A" or "C" syllables. In half of the test pairs, the rule-words differed from the class-word in their "A" syllables; in the remaining pairs, the items differed in their "C" syllables. Appendix C lists the 24 test pairs. Test pairs were presented in random order.

Results

As shown in Figure 2, participants preferred rule-words to class-words (preference for rule-words: $M = 58.1\%$, $SD = 7.0\%$), $t(13) = 4.6$, $p = .0003$, Cohen's $d = 1.1$, $CI_{.95} = 54.3\%, 61.8\%$. This preference did not depend on whether the items differed in their "A" or their "C" syllable, $t(13) = 0.2$, $p > .8$, Cohen's $d = 0.04$, *ns* (paired *t* test).

Discussion

In Experiment 3, participants preferred rule-words to class-words and were thus sensitive to TPs among nonadjacent middle syllables. This suggests that statistical computations may not be limited in the same way as the class-based generalizations. At the same time, this experiment shows that participants can process word-medial syllables, suggesting that the failure to generalize the word-medial class-based regularities was not due to a psychophysical impairment for processing word-medial syllables.

It is interesting to note that the performance in Experiment 3 was comparable to that in Endress and Bonatti's (2007) Experiment 12. In the latter experiment, participants had to choose between trisyllabic rule-words and class-words after familiarization with a segmented 2-min stream. As in Experiment 3, participants thus had to track nonadjacent associations between syllables with a lag of one syllable; in contrast to Experiment 3, however, the crucial syllables were in edges. Together, these results thus suggest that the



Figure 2. *Results of Experiment 3. The bar represents the sample average, the error bar the standard error from the mean, and the dotted line the chance level of 50%. Participants preferred rule-words to class-words (and were thus sensitive to transitional probabilities, TPs, between nonadjacent syllables) also when the critical syllables were in word-middles.*

impairment for generalizations in middles may not be entirely due to problems memorizing or encoding items in edges, but at least partly to processes inherent to the generalizations and thus to the processes underlying memory for positions.

GENERAL DISCUSSION

There is overwhelming evidence that learners can perform powerful statistical computations over fluent speech to extract the underlying words (e.g., Aslin et al., 1998; Saffran et al., 1996). However, learners do not acquire only the words of their native language, but also its grammar. There are indications that grammar-like regularities can also be extracted from fluent speech (Endress & Bonatti, 2007; Peña et al., 2002). In Endress and Bonatti's (2007) experiments, for example, participants learned that the first and the last syllables of each word had to belong to two distinct syllable classes. These classes may be either classes like nouns and verbs in language, or they may merely be the lists of syllables that can occur initially or finally and thus in the word-edges. The latter possibility is particularly plausible because memory for positions is encoded relative to the edges as anchor points (e.g., Henson, 1998) and because the crucial syllables in the aforementioned experiments (those that had to belong to distinct classes) were located in edge positions. If so, participants should learn similar generalizations much better when the crucial syllables are in edge positions than when they are in other positions. Alternatively, if participants have learned classes such as nouns and verbs in language, one would expect similar generalizations also in nonedge positions, as nouns and verbs are not restricted to edges either.

We tested these possibilities by familiarizing participants with streams of five-syllable words. When familiarized with a stream in which words were separated by silences, participants generalized the class-based regularity when the crucial syllables were in the word-edges, but not when they were in the word-middles. When familiarized with continuous streams, in contrast, participants did not generalize the class-based regularity, but rather preferred items that had occurred in the familiarization streams but violated the class-based regularity—irrespective of whether the crucial syllables were in word-edges or word-middles. As participants generalized the class-rule only when the critical syllables were in edges (and when familiarized with a segmented stream), also the class-based generalizations observed by Endress and Bonatti (2007) may have been carried by the edge syllables. In contrast to the generalizations, participants were sensitive to TPs between nonadjacent syllables also in word-middles, suggesting that the corresponding statistical computations may not be constrained in the same way as the generalizations.

Overall, two kinds of mechanisms may thus explain the results following Peña et al.'s (2002) publication: An edge-based, positional memory mechanism allowing participants to track which syllables occurred in edges may account for the generalizations, while other mechanisms may track different forms of co-occurrence statistics among syllables.

Four puzzles solved

Several proponents of "general associationist mechanisms" (e.g., Perruchet et al., 2004; Seidenberg et al., 2002) have suggested that such mechanisms may account for Peña et al.'s (2002) and Endress and Bonatti's (2007) results. However, these proposals only stated that the mechanisms of the generalizations may be associationist but not what they actually may be. Here, we propose two actual mechanisms that seem to account for all aspects of Peña et al.'s (2002) and Endress and Bonatti's (2007) data—namely, a mechanism tracking the co-occurrence statistics among syllables such as transitional probabilities (e.g., Aslin et al., 1998; Saffran et al., 1996) and a second, edge-based mechanism encoding the positions of syllables once edge-cues are available. Given these mechanisms, we can provide several general reasons why these results provide a challenge to associationist, single-mechanism models.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Downloaded By: [Harvard College] At: 19:16 6 May 2009

The first puzzle for single-mechanism, associationist accounts is why statistical computations are readily observed with continuous speech streams, while the generalizations require segmentation cues to emerge. In contrast, if the generalizations are computed by an edge-based positional mechanism, it becomes clear why the silences were required for the generalizations: Without the silences, there would be no edges, and positional memories could not be constructed—since the latter are edge-based.

The second puzzle is why class-words should ever be preferred to part-words, as class-words never occurred during familiarization and contained syllables from four different words while part-words occurred in the stream. A positional memory mechanism easily accounts for a preference for class-words (and why they can be accepted at all), as it is well known that learners can recognize the sequential positions of items also when the items are transplanted to a new sequence (e.g., Hicks et al., 1966; Schulz, 1955).

The third puzzle solved by our model is the time course of the generalizations. The negative correlation between the preference for class-words versus part-words and the familiarization duration, and the inversion of this preference after long exposure durations, is easily explained by a dual-mechanism account. Participants should be familiar with class-words early on because edges, in addition to having positional codes, are salient, and edge-based generalizations may thus be fast. Part-words (the alternative choice), however, can become familiar only through tracking the syllable distribution in the speech streams; as such a distributional analysis presumably takes time to strengthen the memory representations of part-words, one would predict that the preference for class-words decreases with longer familiarization durations. For a single-mechanism model, however, such a reversal is hard to explain.

The experiments presented here pose yet another puzzle to single-mechanism, associationist accounts. Experiments 1 and 2 showed that generalizations are observed predominantly in edges, while Experiment 3 revealed that co-occurrence statistics are tracked in middles (in fact, to the same extent as in Endress and Bonatti's, 2007, Experiment 12). However, it seems problematic to postulate that a single-route, "general associative" mechanism should be constrained to fail in middles (for generalizations) and, at the same time, to work well in middles (for associations). If the generalizations are due to a mechanism of positional memory, in contrast, no such contradiction follows: Different mechanisms may break down under different conditions.

In sum, our results suggest a simple dual-mechanism account of Peña et al.'s (2002) results: The generalizations may be due to special positional codes for edges similar to those thought to be crucial to positional memory (e.g., Henson, 1998); syllables then get linked to these codes in some way, possibly through some form of association. These codes may thus allow participants to track which syllables occurred in the edges. At the same time, a slower mechanism analyses the syllable distribution, for instance by computing co-occurrence statistics.

Edges in artificial and natural grammars

Our results suggest that the class-based generalizations observed by Peña et al. (2002) and Endress and Bonatti (2007) were due to a simple and specialized mechanism that provides positional codes in edges. Edges are usually considered uninteresting confounds to be controlled for (e.g., Redington & Chater, 1996, but see, e.g., Dienes, Broadbent, & Berry, 1991; Johnstone & Shanks, 1999; Shanks, Johnstone, & Staggs, 1997, who used them as an explanation for generalization in other artificial-grammar-learning experiments). However, as we argue below, edge-based mechanisms are the psychological basis of surprisingly complex generalizations.

Examples come from artificial-grammar-learning experiments and linguistics. One unexpected conclusion from our experiments is that the generalizations in Peña et al.'s (2002) experiments are similar to those in the venerable MN/PQ problem (e.g., Braine, 1963, 1966; Smith, 1966,

1967, 1969). In these experiments, participants were familiarized with bigrams of four types of items, dubbed M, N, P, and Q. The bigrams always had the form m_in_j or p_iq_j; that is, M items were always followed by N items, and P items by Q items. Still, participants learned only that the Ms and Ps had to occur initially and Ns and Qs finally, but they did not reject strings such as m_iq_j, although M items were never followed by Q items. Hence, it has been concluded by these authors that participants essentially learned the sequential positions in which the items had to appear, which appears to be what Peña et al.'s (2002) participants learned too.

Another example for the importance of edges in artificial-grammar learning comes from Marcus et al.'s (1999) studies. These authors familiarized young infants with syllable sequences conforming to one of the grammars ABA, AAB, or ABB (e.g., a sequence like "wo–fe–fe" would conform to ABB) and showed that the infants generalize these grammars to new syllables. The repetitions in these structures, however, occurred in the sequence-edges. Using seven-syllable sequences, Endress et al. (2005) showed that participants generalize repetition-based grammars much more readily when the repetitions are in edges than when they are in middles, even though participants could process syllables in sequence-middles as well as in edge positions when they were not required to draw generalizations. These results suggest that positional regularities are learned predominantly in edges, even if participants have no problems processing the items that occur in other positions.

Edges are also important for most linguistic regularities that appeal to positions of items. Of course, in natural speech edges are usually not defined by silences of the kind used here, but we suggest that edges may be provided by prosodic break-points of various kinds and by utterance boundaries. Some examples for edge-based regularities come from phonology. For instance, the location of word stress is defined relative to either the left or the right edge of words; it may be word-initial (as in Hungarian) or word-final (as in French), or on another syllable counted from the right edge (e.g., the second from the last in Italian). In contrast, languages do not appeal to word-middles—for example, by stating that stress falls on the middle syllable (e.g., Halle & Vergnaud, 1987; Hayes, 1995; Kager, 1995).

Also morphological processes such as affixation often appeal to edges: Many languages have suffixes and prefixes, but infixes are rare (e.g., Greenberg, 1957; Julien, 2002). If prefixation and suffixation rely on edge-based positional codes, one can easily explain this observation. Finally, edges are also crucial for interfacing different levels of representation. While both being hierarchical, morphosyntactic and phonological representations have distinct hierarchies; for example, the plural [s] in English is a morpheme, but it is not a syllable. In examples such as these, where constituents of the two hierarchies do not coincide, at least one of the edges of the constituents must be aligned (McCarthy & Prince, 1993; Nespor & Vogel, 1986); for example, the right edge of the [s] morpheme always coincides with the right edge of a syllable. Edges thus seem to mediate between different hierarchies and levels of representations; in some cases, they may be the common currency by which these hierarchies can be coordinated.

As hierarchical processing seems to be a fundamental property of human (and other animals') cognition (e.g., Cooper & Shallice, 2006; Fodor, 1983; Gallistel, 1990, 2000; Marr, 1982; Marr & Nishihara, 1992), such a function may be surprising for a mechanism as simple as an "edge-detector". Nevertheless, it highlights that even very simple perceptual or memory primitives (such as edge-based positional codes) may explain not only generalizations with artificial grammars as in our experiments; rather (and despite the truism that it takes more to learn a language than having an edge-detector), such primitives may also reflect some important aspects of linguistic structure that otherwise remain unexplained. This gives hope that considering other cognitive constraints may also explain other structural generalizations and may ultimately lead to a better understanding of language acquisition.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Original manuscript received 30 July 2008
Accepted revision received 4 December 2008
First published online day month year

Downloaded By: [Harvard College] At: 19:16 6 May 2009

REFERENCES

Aslin, R. N., Saffran, J., & Newport, E. L. (1998). Computation of conditional probability statistics by 8-month-old infants. *Psychological Science*, *9*, 321–324.

Balaguer, R. D. D., Toro, J. M., Rodriguez-Fornells, A., & Bachoud-Lévi, A.-C. (2007). Different neurophysiological mechanisms underlying word and rule extraction from speech. *PLoS ONE*, *2*(11), e1175. doi:10.1371/journal.pone.0001175

Braine, M. (1963). On learning the grammatical order of words. *Psychological Review*, *70*, 323–348.

Braine, M. (1966). Learning the positions of words relative to a marker element. *Journal of Experimental Psychology*, *72*, 532–540.

Braine, M. (1987). What is learned in acquiring word classes—a step toward an acquisition theory. In B. MacWhinney (Ed.), *Mechanisms of language acquisition* (pp. 65–87). Hillsdale, NJ: Lawrence Erlbaum Associates.

Cooper, R. P., & Shallice, T. (2006). Hierarchical schemas and goals in the control of sequential behavior. *Psychological Review*, *113*, 887–916; discussion, 917–931.

Dienes, Z., Broadbent, D., & Berry, D. (1991). Implicit and explicit knowledge bases in artificial grammar learning. *Journal of Experimental Psychology Learning, Memory & Cognition*, *17*, 875–887.

Dutoit, T., Pagel, V., Pierret, N., Bataille, F., & van der Vreken, O. (1996). The MBROLA project: Towards a set of high-quality speech synthesizers free of use for non-commercial purposes. In *Proceedings of the Fourth International Conference on Spoken Language Processing* (Vol. 3, pp. 1393–1396). Philadelphia.

Endress, A. D., & Bonatti, L. L. (2007). Rapid learning of syllable classes from a perceptually continuous speech stream. *Cognition*, *105*, 247–299.

Endress, A. D., & Mehler, J. (in press). Perceptual constraints in phonotactic learning. *Journal of Experimental Psychology: Human Perception and Performance*.

Endress, A. D., Scholl, B. J., & Mehler, J. (2005). The role of salience in the extraction of algebraic rules. *Journal of Experimental Psychology: General*, *134*, 406–419.

Fodor, J. A. (1975). *The language of thought*. Cambridge, MA: Harvard University Press.

Fodor, J. A. (1983). *The modularity of mind*. Cambridge, MA: MIT Press.

Fodor, J. A., & Pylyshyn, Z. W. (1988). Connectionism and cognitive architecture: A critical analysis. *Cognition*, *28*, 3–71.

Gallistel, C. (1990). *The organization of learning*. Cambridge, MA: MIT Press.

Gallistel, C. (2000). The replacement of general-purpose learning models with adaptively specialized learning modules. In M. Gazzaniga (Ed.), *The cognitive neurosciences* (2nd ed., pp. 1179–1191). Cambridge, MA: MIT Press.

Gerken, L., Wilson, R., & Lewis, W. (2005). Infants can use distributional cues to form syntactic categories. *Journal of Child Language*, *32*, 249–268.

Gómez, R. L., & Gerken, L. (1999). Artificial grammar learning by 1-year-olds leads to specific and abstract knowledge. *Cognition*, *70*, 109–135.

Gómez, R. L., & Lakusta, L. (2004). A first step in form-based category abstraction by 12-month-old infants. *Developmental Science*, *7*, 567–580.

Greenberg, J. (1957). *Essays in linguistics*. Chicago: University of Chicago Press.

Halle, M., & Vergnaud, J.-R. (1987). *An essay on stress*. MIT Press: Cambridge, MA.

Hauser, M. D., Newport, E. L., & Aslin, R. N. (2001). Segmentation of the speech stream in a non-human primate: Statistical learning in cotton-top tamarins. *Cognition*, *78*, B53–B64.

Hayes, B. (1995). *Metrical stress theory: Principles and case studies*. Chicago: University of Chicago Press.

Henson, R. (1998). Short-term memory for serial order: The start-end model. *Cognitive Psychology*, *36*, 73–137.

Henson, R. (1999). Positional information in short-term memory: Relative or absolute? *Memory and Cognition*, *27*, 915–927.

Hicks, R., Hakes, D., & Young, R. (1966). Generalization of serial position in rote serial learning. *Journal of Experimental Psychology*, *71*, 916–917.

Hitch, G. J., Burgess, N., Towse, J. N., & Culpin, V. (1996). Temporal grouping effects in immediate recall: A working memory analysis. *Quarterly Journal of Experimental Psychology: Human Experimental Psychology*, *49*, 116–139.

Johnstone, T., & Shanks, D. R. (1999). Two mechanisms in implicit artificial grammar learning? Comment on Meulemans and van der Linden

(1997). *Journal of Experimental Psychology: Learning, Memory, and Cognition*, *25*, 524–531.

Julien, M. (2002). *Syntactic heads and word formation*. New York: Oxford University Press.

Jusczyk, P. W., Hohne, E., & Bauman, A. (1999). Infants' sensitivity to allophonic cues for word segmentation. *Perception and Psychophysics*, *61*, 1465–1476.

Kager, R. (1995). Consequences of catalexis. In H. van der Hulst & J. van de Weijer (Eds.), *Leiden in last: HIL phonology papers I* (pp. 269–298). The Hague, The Netherlands: Holland Academic Graphics.

Lehman, J. F., Laird, J. E., & Rosenbloom, P. (1998). A gentle introduction to soar, an architecture for human cognition. In D. Scarborough & S. Sternberg (Eds.), *An invitation to cognitive science* (2nd ed., Vol. 4, pp. 211–253). Cambridge, MA: MIT Press.

Marcus, G. F., Vijayan, S., Rao, S. B., & Vishton, P. (1999). Rule learning by seven-month-old infants. *Science*, *283*, 77–80.

Marr, D. (1982). *Vision*. San Francisco: W. H. Freeman and Company.

Marr, D., & Nishihara, H. K. (1992). Visual information processing: Artificial intelligence and the sensorium of sight. In S. M. Kosslyn & R. A. Andersen (Eds.), *Frontiers in cognitive neuroscience* (pp. 165–186). Cambridge, MA: MIT Press. (Reprinted from *Technology Review, 81*, 2–23, 1978).

Mattys, S. L., & Jusczyk, P. W. (2001). Phonotactic cues for segmentation of fluent speech by infants. *Cognition*, *78*, 91–121.

Mattys, S. L., Jusczyk, P. W., Luce, P., & Morgan, J. L. (1999). Phonotactic and prosodic effects on word segmentation in infants. *Cognitive Psychology*, *38*, 465–494.

McCarthy, J. J., & Prince, A. (1993). Generalized alignment. In G. Booij & J. van Marle (Eds.), *Yearbook of morphology* (pp. 79–153). Boston, MA: Kluwer.

Miller, G. A.(1958). Free recall of redundant strings of letters. *Journal of Experimental Psychology*, *56*, 485–491.

Mintz, T. H. (2002). Category induction from distributional cues in an artificial language. *Memory and Cognition*, *30*, 678–686.

Monaghan, P., Chater, N., & Christiansen, M. H. (2005). The differential role of phonological and distributional cues in grammatical categorisation. *Cognition*, **96**, 143–182.

Mueller, J. L., Bahlmann, J., & Friederici, A. D. (2008). The role of pause cues in language learning: The emergence of event-related potentials related to sequence processing. *Journal of Cognitive Neuroscience*, *20*, 892–905.

Nespor, M., & Vogel, I. (1986). *Prosodic phonology*. Dordrecht, The Netherlands: Foris.

Newell, A. (1980). Physical symbol systems. *Cognitive Science*, *4*, 135–183.

Newell, A. (1990). *Unified theories of cognition*. Cambridge, MA: Harvard University Press.

Ng, H. L., & Maybery, M. T. (2002). Grouping in short-term verbal memory: Is position coded temporally? *Quarterly Journal of Experimental Psychology: Section A*, *55*, 391–424.

Pacton, S., & Perruchet, P. (2008). An attention-based associative account of adjacent and nonadjacent dependency learning. *Journal of Experimental Psychology. Learning, Memory and Cognition*, *34*, 80–96.

Peña, M., Bonatti, L. L., Nespor, M., & Mehler, J. (2002). Signal-driven computations in speech processing. *Science*, *298*, 604–607.

Perruchet, P., Tyler, M. D., Galland, N., & Peereman, R. (2004). Learning nonadjacent dependencies: No need for algebraic-like computations. *Journal of Experimental Psychology: General*, *133*, 573–583.

Reber, A. S. (1967). Implicit learning of artificial grammars. *Journal of Verbal Learning and Verbal Behavior*, *6*, 855–863.

Reber, A. S. (1969). Transfer of syntactic structure in synthetic languages. *Journal of Experimental Psychology*, *81*, 115–119.

Redington, M., & Chater, N. (1996). Transfer in artificial grammar learning: A reevaluation. *Journal of Experimental Psychology: General*, *125*, 123–138.

Redington, M., Chater, N., & Finch, S. (1998). Distributional information: A powerful cue for acquiring syntactic categories. *Cognitive Science*, *22*, 425–469.

Saffran, J. R. (2001). Words in a sea of sounds: The output of infant statistical learning. *Cognition*, *81*, 149–169.

Saffran, J. R., Aslin, R. N., & Newport, E. L. (1996). Statistical learning by 8-month-old infants. *Science*, *274*, 1926–1928.

Schulz, R. W. (1955). Generalization of serial position in rote serial learning. *Journal of Experimental Psychology*, *49*, 267–272.

Seidenberg, M. S., MacDonald, M. C., & Saffran, J. R. (2002). Does grammar start where statistics stop? *Science*, *298*, 553–554.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

Shanks, D. R., Johnstone, T., & Staggs, L. (1997). Abstraction processes in artificial grammar learning. *Quarterly Journal of Experimental Psychology A*, *50*, 216–252.

Shukla, M., Nespor, M., & Mehler, J. (2007). An interaction between prosody and statistics in the segmentation of fluent speech. *Cognitive Psychology*, *54*, 1–32.

Smith, K. (1966). Grammatical intrusions in the recall of structured letter pairs: Mediated transfer or position learning? *Journal of Experimental Psychology*, *72*, 580–588.

Smith, K. (1967). Rule-governed intrusions in the free recall of structured letter pairs. *Journal of Experimental Psychology*, *73*, 162–164.

Smith, K. (1969). Learning co-occurrence restrictions: Rule learning or rote learning. *Journal of Verbal Learning and Verbal Behavior*, *8*, 319–321.

Downloaded By: [Harvard College] At: 19:16 6 May 2009

APPENDIX A

Test Items Used in Experiment 1a

Table A1. *Test pairs used in Experiment 1*

Class-word	*Part-word*	*Class-word type*	*Part-word type*
bamydonade	dogudebafa	$A_iA_kYC_lC_j$	$YZC_i\mid A_jX$
Rilodofugi	dogugiRiRe	$A_iC_kYA_lC_j$	$YZC_i\mid A_jX$
badelyRigi	lygugibaRe	$A_iC_kYA_lC_j$	$YZC_l\mid A_jX$
Rimydofulo	ziloRizudo	$A_iA_kYA_lC_j$	$ZC_i\mid A_jXY$
fugidoRilo	dogulofufa	$A_iC_kYA_lC_j$	$YZC_i\mid A_jX$
bafunemyna	nezinabazu	$A_iA_kYA_lC_j$	$YZC_i\mid A_jX$
mylolynade	lygudemyzu	$A_iC_kYC_lC_j$	$YZC_i\mid A_jX$
bagineRide	gudebafane	$A_iC_kYA_lC_j$	$ZC_i\mid A_jXY$
bafulynagi	zigibafaly	$A_iA_kYC_lC_j$	$ZC_i\mid A_jXY$
myRilydelo	lygulomyzu	$A_iA_kYC_lC_j$	$YZC_i\mid A_jX$
Ridenegilo	neboloRiRe	$A_iC_kYC_lC_j$	$YZC_i\mid A_jX$
fulolygina	gunafufaly	$A_iC_kYC_lC_j$	$ZC_i\mid A_jXY$
fubalygina	lygunafuRe	$A_iA_kYC_lC_j$	$YZC_i\mid A_jX$
mybanedena	gunamyzune	$A_iA_kYC_lC_j$	$ZC_i\mid A_jXY$
Ribanemyde	nezideRifa	$A_iA_kYA_lC_j$	$YZC_i\mid A_jX$
fuRinemylo	gulofuzune	$A_iA_kYA_lC_j$	$ZC_i\mid A_jXY$
Ridenelogi	gugiRifane	$A_iC_kYC_lC_j$	$ZC_i\mid A_jXY$
bagidodena	bonabaRedo	$A_iC_kYC_lC_j$	$ZC_i\mid A_jXY$
myfudobana	dozinamyfa	$A_iA_kYA_lC_j$	$YZC_i\mid A_jX$
myRilyfulo	zilomyRely	$A_iA_kYA_lC_j$	$ZC_i\mid A_jXY$
mynadobade	bodemyzudo	$A_iC_kYA_lC_j$	$ZC_j\mid A_jXY$
Rimydolode	bodeRiRedo	$A_iA_kYC_lC_j$	$ZC_i\mid A_jXY$
funadobagi	zigifuRedo	$A_iC_kYA_lC_j$	$ZC_i\mid A_jXY$
funanelogi	nezigifuRe	$A_iC_kYC_lC_j$	$YZC_i\mid A_jX$

APPENDIX B

Test Items used in Experiment 1b

Table B1. *Test Pairs used in Experiment 2.*

Class-word	*Part-word*	*Class-word type*	*Part-word type*	*TP ($Z \rightarrow X$)*
giRidolofu	dolofaguRi	$C_kA_iYC_jA_l$	$YC_iZ\|XA_j$	high
baRilygide	lygifazuRi	$A_kA_iYC_jC_l$	$YC_iZ\|XA_j$	high
Rifudologi	dolofagufu	$A_kA_iYC_jC_l$	$YC_iZ\|XA_j$	high
loRilygide	ginaguRily	$C_kA_iYC_jC_l$	$C_iZ\| XA_jY$	high
gibanedeRi	debogubane	$C_kA_iYC_jA_l$	$C_iZ\| XA_jY$	low
lomylyzide	zinaRemyly	$C_kA_iYC_jC_l$	$C_iZ\| XA_jY$	high
bamydodeRi	deboRemydo	$A_kA_iYC_jA_l$	$C_iZ\| XA_jY$	high
myfuneloRi	lofazufune	$A_kA_iYC_jA_l$	$C_iZ\| XA_jY$	high
myRinedelo	nedenazuRi	$A_kA_iYC_jC_l$	$YC_iZ\|XA_j$	low
deRidologi	lofaReRido	$C_kA_iYC_jC_l$	$C_iZ\| XA_jY$	low
zifudogiba	doginagufu	$C_kA_iYC_jA_l$	$YC_iZ\|XA_j$	high
zimylylofu	lylobozumy	$C_kA_iYC_jA_l$	$YC_iZ\|XA_j$	high
zimynedelo	nedeboRemy	$C_kA_iYC_jC_l$	$YC_iZ\|XA_j$	high
mybanezide	zibozubane	$A_kA_iYC_jC_l$	$C_iZ\| XA_jY$	high
fubanegizi	ginazubane	$A_kA_iYC_jC_l$	$C_iZ\| XA_jY$	low
bafudozigi	zibozufudo	$A_kA_iYC_jC_l$	$C_iZ\| XA_jY$	high
debanegizi	negiboReba	$C_kA_iYC_jC_l$	$YC_iZ\|XA_j$	high
lomylyzifu	lyzifaRemy	$C_kA_iYC_jA_l$	$YC_iZ\|XA_j$	low
Rifulygiba	gifaRefuly	$A_kA_iYC_jA_l$	$C_iZ\| XA_jY$	low
mybanezifu	nezinaReba	$A_kA_iYC_jA_l$	$YC_iZ\|XA_j$	high
baRilydemy	defaguRily	$A_kA_iYC_jA_l$	$C_iZ\| XA_jY$	high
gifulyzilo	lyzibogufu	$C_kA_iYC_jC_l$	$YC_iZ\|XA_j$	low
fumydoloRi	dolonazumy	$A_kA_iYC_jA_l$	$YC_iZ\|XA_j$	low
zibalydemy	denagubaly	$C_kA_iYC_jA_l$	$C_iZ\| XA_jY$	high

Downloaded By: [Harvard College] At: 19:16 6 May 2009

APPENDIX C

Test Items Used in Experiment 3

Table C1. *Test pairs used in Experiment 4. If the position of the shared syllable is initial, the test items differ only in the penultimate syllable (i.e., the 'C' syllable); otherwise, the items differ only in their second syllable (i.e., their 'A' syllable).*

Rule-word	*Class-word*	*Class-word type*	*Position of the shared syllables*
Ribadolode	Rimydolode	$A_kA_iYC_jC_l$	final
fuRinezimy	fubanezimy	$A_kA_iYC_jA_l$	final
myfulydeRi	mybalydeRi	$A_kA_iYC_jA_l$	final
zimynegiba	zifunegiba	$C_kA_iYC_jA_l$	final
bafulydemy	baRilydemy	$A_kA_iYC_jA_l$	final
gibanelode	giRinelode	$C_kA_iYC_jC_l$	final
loRinezifu	loRinegifu	$C_kA_iYC_jA_l$	initial
giRinezilo	gifunezilo	$C_kA_iYC_jC_l$	final
fumydogiRi	fubadogiRi	$A_kA_iYC_jA_l$	final
bafudodezi	bafudogizi	$A_kA_iYC_jC_l$	initial
demynegilo	deRinegilo	$C_kA_iYC_jC_l$	final
mybadolode	mybadozide	$A_kA_iYC_jC_l$	initial
Ribalylogi	Ribalydegi	$A_kA_iYC_jC_l$	initial
deRilyzigi	deRilylogi	$C_kA_iYC_jC_l$	initial
fubalylozi	fubalygizi	$A_kA_iYC_jC_l$	initial
bamynegifu	bamynezifu	$A_kA_iYC_jA_l$	initial
zifulydelo	zimylydelo	$C_kA_iYC_jC_l$	final
zibanelomy	zifunelomy	$C_kA_iYC_jA_l$	final
lofudodegi	lofudozigi	$C_kA_iYC_jC_l$	initial
myfudodeRi	myfudoloRi	$A_kA_iYC_jA_l$	initial
Rimydogilo	Rimydodelo	$A_kA_iYC_jC_l$	initial
giRilyziba	giRilydeba	$C_kA_iYC_jA_l$	initial
deRilyziba	demylyziba	$C_kA_iYC_jA_l$	final
zimydogifu	zimydolofu	$C_kA_iYC_jA_l$	initial

Downloaded By: [Harvard College] At: 19:16 6 May 2009